

SECTION 01 43 38

FIELD SAMPLES AND MOCK-UPS

PART 1 – GENERAL

1.01 SECTION INCLUDES

- A. Field samples and mock-ups.

1.02 MEASUREMENT AND PAYMENT

- A. Separate measurement or payment will not be made for work required under this Section. All costs in connection with the work specified herein will be considered to be included with the related item of work in the Bid Schedule of the Bid Form, or incidental to the Work.

1.03 FIELD SAMPLES AND MOCK-UPS

- A. Field samples and mock-ups shall be prepared at the jobsite by the Contractor as specified in the various Sections of these Specifications. When approved by the Engineer or specified, prepare mock-ups at another location provided by the Contractor. Affected work shall not be started until the Engineer has approved the field samples and mock-ups in writing.
- B. Construct and prepare field samples and jobsite mock-ups at designated locations at the jobsite or on the structure as directed by the Engineer.
 - 1. The Contractor shall have authorized product manufacturer's representatives inspect and approve field samples and mock-ups, which involve their materials, for proper application or installation of the materials in accordance with their respective instructions and recommendations for the conditions or circumstances involved in the application or installation.
 - 2. The Contractor shall make arrangements with the respective authorized product manufacturer's representatives to provide job or field service as specified in Section 01 43 00, Quality Assurance.
- C. Notify the Engineer when mock-ups constructed at other locations are ready for review. Maintain mock-up intact until related work has been installed at the jobsite or as otherwise approved by the Engineer.
- C. Construct, prepare, and modify samples and mock-ups as may be required, as determined by the Engineer, until desired features including textures, finishes, and colors are obtained and approved. Approved samples and mock-ups shall serve as the standards of quality for the various affected units of work.
- D. Field Samples and Mock-Ups for Approval of Textures, Finishes, and Colors: Preserve approved field samples and mock-ups for comparison purposes until the affected work is completed and accepted by the District. Finished work shall match the approved field samples and mock-ups.

1.04 NONCONFORMANCE

- A. Completed work which does not exactly match approved field samples and mock-ups will be rejected, and shall be replaced with work which does exactly match the approved field samples and mock-ups at the Contractor's expense.
- B. If the Contractor elects to start work before the Engineer has approved the related field samples or mock-ups, the Contractor does so at the risk of having the work rejected by the Engineer without compensation.

1.05 REMOVAL AFTER COMPLETION: Field samples and jobsite mock-ups shall be removed from the jobsite and structures after completion and acceptance of the affected work or otherwise as directed by the Engineer.

PART 2 – PRODUCTS

Not Used

PART 3 – EXECUTION

Not Used

END OF SECTION 01 45 17