

**BART Agreement Number: 6M8144**

**Approval Date: 10/25/21**

**Revised Date: 03/04/24**

**Work Plan No. B.06-03 – W-Line Tunnel Water Mitigation – Engineering Support  
During Construction**

**Scope:**

The construction work by BART Maintenance forces consists of the injection of chemical grout into cracks/joints in M-Line and W Line concrete cut-and-cover tunnel structures. The consultant will continue updating the remedial work plan and procedures and will provide weekly observation and documentation of the tunnel leak grouting work. The consultant will work with BART's Maintenance and Engineering team to provide input in adjusting the grouting process for unforeseen field conditions.

**Prime: HNTB + FMG JV**

<b>Subconsultant</b>	<b>Amount</b>	<b>DBE (Y/N)</b>	<b>SBE (Y/N)</b>
Gall Zeidler Consultants	\$ 25,363	N	N

**Total Work Plan Value: \$ 221,806**